



FRESNO COUNTY FIRE

PROTECTION DISTRICT

210 South Academy Avenue
Sanger, California 93657
Telephone: (559) 493-4300
Fax: (559) 875-8473

REQUEST FOR QUOTE 2024-05-101

Fresno County Fire Protection District is soliciting quotes for the provision for all equipment, materials, and labor necessary for a durable and high-performance concrete and asphalt replacement that will withstand heavy loads high foot and vehicle traffic. Approximate square footage for the Concrete Pad is 6,080 Sq Ft. we are also exploring our options for concrete work [**Fiber Reinforcement Vs Rebar**]. Asphalt Replacement is approximately 35,750 Sq Ft. This project includes two construction areas.

Please provide us with your best quote for the following services:

Slab to meet or exceed the following requirements

1. Fiber reinforcement with expansion joints cut every 10' each way, 8" thick 4000 PSI
2. Rebar #3 @ 18 expansion joints every 12' to 15' each way, 6" thick 4000 PSI
3. Concrete apron 50' long
4. Smooth finish

Asphalt to meet or exceed the following requirements

1. 4" asphalt over 8" base rock section
2. ¾" aggregate for both lifts on the asphalt

CONTRACTOR REQUIREMENTS: The following requirements apply to all contractors for all public work projects in the Fresno County Fire Protection District. Please include the following information in your proposal:

- Whether your quotes are inclusive or exclusive of sales taxes; if not otherwise stated, we will assume your quotes are inclusive of state taxes
- Your company's experience in the construction industry
- Relevant qualifications and certifications
- A timeline for delivery from receipt of our purchase order to receipt of your shipment; this timeframe will be a condition of any purchase order made; a timeline for completion
- Any references or examples of similar projects you have completed in the past.
- Your DIR registration Number.
- A list of all planned subcontractors, with name of company, license numbers, DIR number, and total dollar amount of subcontract
- A detailed breakdown of your costs for each service, including any additional charges or fees that may apply
- Your terms of payment

All price quotation must be firm and state when they expire.

We will be evaluating proposals based on price, quality, and your company's ability to meet our specific needs. Please submit your proposal via email no later than 4:00PM February 17th, 2025. If you have any questions or require additional information, please do not hesitate to contact us.

Thank you for your time and consideration. We look forward to receiving your proposal.

Sincerely,
Louisa Alonzo
Fresno County Fire Protection District
559-493-4361
louisa.alonzo@fire.ca.gov

Attachments:

- Exhibit A Site Plans

New Concrete and Asphalt Replacement





Shop

Station 82

Date: January 28, 2025

The displayed data is approximate and should only be used for informational purpose.

Legend

-  New Concrete (Approx. 6,080 Sq Ft)
-  Asphalt Replacement (Approx. 35,750 Sq Ft)

0 50 100
US Feet